FRENCH ROCKS DIVISION. [ADVERTISEMENT.

Notification dated 19th April 1895.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks Division, up to 28th April 1895, for constructing an aqueduct at 22¼ mile of Chik Devarayasagar Channel. An approximate estimate of quantities is given below. These quantities are not guaranteed The work should be completed by the end of May 1896.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office, at French Rocks between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200, two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an aqueduct at 22¼ mile of Chik Devarayasagar Channel" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. No tender will be considered which does not offer item per item in the blank columns under "rates."

7. No tender will be considered which is not accompanied by a certificate to the effect that the Contractor has visited the site of the works and has made himself acquainted with the cost of materials, labor. &c, ruling in the neighbourhood and that his tender is based upon the information so gained. Such certificate should bear the signature of the D. P. W. Sub-Divisional Officer or the signature of a subordinate of the Department.

8. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

9. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

10. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work.	*Per.*	*Quantity.* Rs.
Clearing site .. .. Lump sum		
Earthwork Excavation	C. Yds.	858
Surki concrete	C. Ft.	5,697
Brick in surki mortar	C. Ft.	24,742
Do Archwork	C. Ft.	2,289
Plastering with surki mortar	Sqr.	61·80
Burnt stone in surki mortar	C. Ft.	2,664
Pointing with surki mortar	Sqr.	22·50
Bough stone work new	C. Yds.	2,151
Cornice work	R. Ft.	297
Slab stones burnt (6" thick)	S. Ft.	1,884
Earthwork raising and with watering and tamping	C. Yds.	12,477
Turfing	Sqr.	280·99
Earthwork draught cutting	C. Yds.	13,624
Jelly packing	C. Yds.	258
Baling water	Lump sum Rupees.	
Centering at ⅛ cost of Archwork	Lump sum Rupees.	
Total ..	....	

THOS. INMAN, *Executive Engineer, French Rocks Division.*

Visitors to the Mysore Government Museum, Bangalore, during the month of March 1895.

Signatures made in—										Total of signatures.		Unable to sign.		Total of visitors.	Daily average, exclusive of Sundays and holidays.
English.		Tamil.	Telugu.	Kanarese.	Hindustani.	Mahrati.	Guzarati.	Nagari.	Malayalam.						
Europeans.	Natives.									Males.	Females.	Men and Boys.	Women and Girls.		
191	821	335	123	664	210	22	22	15	..	2,288	115	9,273	7,875	19,551	752

J. CAMERON, *Superintendent.*